

Project: City of West Columbia HAWK traffic signal project

Owner: City of West Columbia, 200 N 12th Street, PO Box 4044, West Columbia, SC 29171

Receipt Of RFP: The City of West Columbia request for proposals from experienced construction firms for the above referenced project will be received at the West Columbia City Hall, New Brookland Room, 1800 12th Street, West Columbia, SC 29033. Bids will be opened on December 19, 2016 at 3pm. Hand deliveries or ground tracking services such as Fed-Ex shall be sent to Tara Greenwood, Grants Administrator, City of West Columbia, 200 N 12th Street, West Columbia, SC 29171, & all regular mail RFQ submittals via USPS should be mailed to Tara Greenwood, Grants Administrator, City of West Columbia, PO Box 4044, West Columbia, SC 29171.

Submittals shall include and comply with the following:

1. Total cost, project approach, and proposed schedule
2. Proof of General Contractors License
3. Proof of Workers Compensation Insurance
4. Three references from similar projects
5. A maximum of ten pages (both sides of the page may be used) shall be submitted with soft cover binding. No hard cover binders will be accepted. Covers are excluded from page count.
6. ONE (1) ORIGINAL AND THREE (3) COPIES OF YOUR PROPOSAL ARE REQUIRED.
7. Proposals will be received at West Columbia City Hall until 3:00 P.M. local time on the opening date shown.

For additional information, any questions, or requests for clarifications please contact:

Tara Greenwood

Grants Administrator

803-791-1880 ext 628

tgreenwood@westcolumbiasc.gov

Project Description: This project consists of the installation of a HAWK traffic signal design on mast arm structure at the existing crosswalk in front of the House of Raeford facility on US 378 in the City of West Columbia. This crosswalk is located approximately 750 feet west of the intersection of US 378 (Sunset Boulevard) and SC 2 (State Street). This design is displayed on the Traffic Signal plan provided within this document involves the installation of a HAWK pedestrian signal with two (2) mast arms, four (4) vehicle signal heads, two (2) pedestrian countdown heads with push buttons, application of thermoplastic pavement markings for stop bar and crosswalk (existing to be remarked) and signing installation and modification. This project shall be constructed in accordance with the SCDOT 2004 Construction Manual, SCDOT 2007 Standard Specifications, SCDOT Standard Drawing, included SCDOT Special Provisions and included SCDOT approved encroachment permit documents. Upon completion of the project shop drawing of the mast arm design and a red line as-built traffic signal plan shall be provided to the City.

This is a public/private partnership project funding in part by Lexington County C Funds.